

## **Installation**

## **Procedure**

- 1. Mount the ZEPICIII on a shelf or wall.
- 2. Install Primary surge protection in the form of air gap arrestors and shunt-type equalizers on the track and battery leads.
- 3. Connect battery, track and relay drive wiring per the site plans. #6 bond strand is recommended for track wiring.
- Place a 0.06 ohm shunt at the desired activation point. NOTE: The track MUST be shunted before the calibration button is pressed.
- 5. Press and HOLD the Blue RCVR CAL button until the relay drive LED starts blinking. Release the Blue button and the LED will stop blinking and the ZEPIC will automatically begin the calibration process. NOTE: The track shunt MUST remain in place during the calibration process.
- 6. The relay drive will pick (LED on) when the unit has successfully calibrated. NOTE: This process can take up to 45 seconds to complete.

## Verification

- 1. Lift the shunt and relay drive should drop.
- Move the shunt 10ft further out from the calibration point and verify that relay drive does not pick up.
- 3. IMPORTANT:

To insure accurate activation point, always place the shunt BEFORE pressing the RCVR CAL button.

- 4. If the ZEPIC can not achieve calibration, it will blink the relay drive LED 3 times in rapid succession indicating a calibration error. The unit will continuously repeat the calibration procedure (no need to press the Blue button) allowing you to troubleshoot the track circuit, wiring and battery. Once the trouble has been corrected, repeat the calibration procedure in steps 4 6.
- Because the ZEPIC is a 2 wire system, it will activate an equal distance on both sides of the track feed point.

The verification procedure detailed above is a typical method and is not intended to supersede the accepted practice of your railroad.



**Zukinut Enterprises, LLC**